

REPUBLIC OF KENYA

REQUEST FOR QUOTATION

To:

Seller's name and address

.....
.....
.....
.....

Quotation No NYCG/Q282/2016-2017

Date.....10/05/2017...

From:

Buyer's Designation and Address

County Government of Nyamira
Supply Chain Management Office,
P.O. Box 434-40500 NYAMIRA

You are invited to submit a Quotation on materials listed below:

Notes:

costs for

- (a) THIS IS NOT AN ORDER. Read the conditions and instructions on reverse before quoting.
- (b) This quotation should be submitted in a plain wax sealed envelope marked "Quotation No.
for supply of **.PLAYFIELDS UPGRADING**
and be addressed to reach the buyer or placed in the Quotation/Tender box not later than
9.30 a.m. on16/05/2017.....

- (c) Your Quotation should indicate final unit price which includes all delivery, discounts duty and sales tax
- (d) Return the original copy and retain the duplicate for your record.
- (e) Attach proof of KRA registration VAT/PIN certificates
- (f) Attach Business registration/Incorporation of company certificate.
- (g) Fill the attached S33 form.
- (h) Tax Compliance certificate copy
- (i) Attach prove of past experience of similar services/works

Code No.	Item Description	Quoted Amount	Remarks
	Please quote as per the attached BQ for Kemera Ward - Ekerubo Primary School		

FOR OFFICIAL USE ONLY

Opened by: (1) Designation Signature

(2) Designation Signature

(3) Designation Signature

(4) Designation Signature

CONDITIONS

1. The General Conditions of Contract with Government of Kenya apply to this transaction. This form properly submitted constitutes the entire agreement.
2. The offer shall remain for 30 days from the closing date unless otherwise stipulated by the seller.
3. The buyer shall not be bound to accept the lowest or any other offer, and reserves the right to accept any offer in part unless the contract is stipulated by the seller.
4. Samples of offers when required will be provided free, and if not destroyed during tests will, upon request, be Returned at the seller's expenses.

INSTRUCTIONS

1. All entries must be typed or written in ink. Mistakes must not be erased but should be crossed out and corrections be made and initiated by the person signing the quotation.
2. Quote on each item separately, and in units as specified.
3. This form must be signed by a competent person and preferably it should be also rubber stamped.
4. Each quotation should be submitted separately in a sealed envelope with the quotation Number endorsed on the Outside. Descriptive literature or samples of items offered may be forwarded with the quotation.
5. If you do not wish to quote, please endorse the reason on this form and return it, otherwise your name may be deleted from the buyer's mailing list for the items listed hereon.

PLAY FIELDS FOR UPGRADING IN COUNTY WARDS

REPUBLIC OF KENYA



DEPARTMENT OF TRANSPORT, ROADS AND PUBLIC WORKS

**PROPOSED FENCING, CONSTRUCTION OF SHED,
LEVELLING AND GOAL POSTS**

AT

EKERUBO PRIMARY SCHOOL(KEMERA WARD)

PREPARED BY:

COUNTY WORKS OFFICE,

P.O BOX 27-40500, NYAMIRA.

	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>LEVELLING AND GOAL POSTS</u>				
	<u>Levelling</u>				
A	Excavate appropriate depth,back fill and and make up levels, prepare the ground to receive grass,water and maintain till maturity.	15,222	S.M		
	<u>Goal posts (Football, Netball and Volleyball)</u>				
B	Fabricate,deliver and install international fibre standard measurement or other approved alternative (measurement to be determined on site)	10	No		
	TOTAL FOR DRAINAGE AND LEVELLING CARRIED TO GRAND SUMMARY				

GRAND SUMMARY

ITEM	DESCRIPTION	PAGE	OFFICIAL USE	TENDERER'S USE
	-		Kshs	Kshs
1	FENCING	PG 1		
2	SHED	PG 4		
3	LEVELLING AND GOAL POSTS	PG 1		
4	PROVISIONAL SUMS	PG 1		
5	SUB-TOTAL			
6	ADD 16% V.A.T			
	TOTAL TENDER AMOUNT CARRIED TO FORM OF TENDER.....			

NAME OF TENDERER.....

ADDRESS.....

SIGNATURE.....STATUS.....

DATE.....

NAME OF WITNESS.....

ADDRESS.....

SIGNATURE.....

DATE.....

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<p><u>SHED</u> <u>ELEMENT NO 01</u> <u>SUBSTRUCTURES (ALL PROVISIONAL)</u> <u>Excavation and Earthworks</u></p>				
A	Excavate oversite average 200mm deep to remove vegetable soil load up wheel and deposit about 100metres away and later spread and level on site where directed area measuring 3m by 10m	1	Item		
B	Excavate for strip foundation starting from reduced level not exceeding 1.50metres deep commencing from reduced level	32	C.M		
C	<p><u>Hardcore</u> 250mm Thick layer of imported Hardcore filling including levelling and consolidating 150mm layers</p>	30	SM		
D	<p><u>Blinding</u> 50mm Thick quarry dust blinding to the surface of hardcore; rolled smooth to receive polythene sheeting</p>	30	S.M		
E	<p><u>Insecticide treatment</u> Treat surface of harcore with "Premise 2000CC" or other equal and approved anti- termite insecticide applied strictly in accordance with manufactures printed instructions</p>	30	S.M		
F	<p><u>Damp proof membrane</u> 500mm Gauge polythene or other equal and approved plastic sheet damp proof membrane laid over blinding (measured nett- allow for laps)</p>	30	S.M		
G	<p><u>Vibrated reinforced concrete (1:2:4) class 20/20</u> <u>aggregates as described in:-</u> Strip foundation</p>	2	C.M		

H	150mm Thick surface bed	30	S.M		
	<u>Fabric; B.S 4483</u>				
I	Fabric mesh reinforcement to B.S 4483 Ref: A98 including laps tying wire and spacer blocks complete (measured nett- for laps)	30	S.M		
J	Edge of floor slab 75-150mm high	26	L.M		
K	150mm thick burnt clay bricks foundation walling and jointing in cement sand (1:3) mortar and reinforced with and including 20swg x25mm wide hoop iron in every alternate course	23	S.M		
TOTAL FOR SUBSTRUCTURES CARRIED TO SUMMARY					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>SUPERSTRUCTURAL CONSTRUCTION</u>				
A	75mm/3mm thick blade pipes steel stanchions complete with concrete and anchorage	20	L.M		
B	50x 50x 3mm SHS rafters	65	LM		
C	50x 50x 2mm SHS steel purlins bolted onto rafters with appropriate cleats	28	L.M		
D	Gauge 30 box profile iron sheet covering complete with hold down bolts and rubber washers	28	S.M		
	<u>concrete bench</u>				
E.	Seats. Reinforced concrete seats complete with reinforcements and formwork to engineers specifications	12	S.M		
	<u>Painting and Decoration</u>				
F	Allow for spray all the visible steel members using high quality fast dry automotive paint	1	Item		
	Allow for spray painting and careful branding of				

G	the front fascial measuring 6m by 0.4m plain sheet complete with county colours and logo	1	Item		
TOTAL FOR SUPERSTRUCTURES CARRIED TO SUMMARY					

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	- <u>SECTION SUMMARY</u>	<u>From</u>			
	-	<u>Page</u>			
A	- SUBSTRUCTURES	- 1			
B	- SUPERSTRUCTURES	2			
	-				
	-				
TOTAL CONSTRUCTION AND COMPLETION OF SHED CARRIED TO GRAND SUMMARY					

ITEM	DESCRIRPTION	QTY	UNIT	RATE	AMOUNT
	<p><u>FENCING</u> <u>Chain Link & STRAINING WIRE</u></p>				
A	2400mm High 14 Gauge chainlink fence fixed on posts (m.s) at 2000mm centres complete with and including Eight strands straining wire to approval	349	L.M		
B	Ceadar posts of 2400mm high including 300x300 x 600mm deep plain concrete class 25 including all necessary excavations	174	NO		
C	Extra Over ceader posts for straining posts with one strut	15	NO		
D	Ditto with two struts	10	NO		
	TOTAL FOR FENCING CARRIED TO GRAND SUMMARY				